



---

**LIEN & PETERSON ARCHITECTS, INC.**

619 MENOMONIE STREET

PO BOX 925

EAU CLAIRE, WI

54703

TELEPHONE 715 835 7500

FAX 715 835 1411

Email

[admin@2dip.com](mailto:admin@2dip.com)

---

**ADDENDUM NO. 1****DATE:** June 25, 2010**PROJECT:** **SCRUB HUB  
2010 REMODEL  
4508 LONDON ROAD  
EAU CLAIRE, WI**

This addendum to the contract documents is issued to modify, explain, or correct the original Drawings and Specifications and is therefore made a part of the Contract Documents now in your possession. Indicate receipt of Addenda on Proposal. All trades shall review for items relating to their work.

**SPECIFICATIONS**

- Section 03 35 16** Omit this section
- Section 04 05 13** Line 5, Page 04 05 13-2. Add 'Sienna Stack ledge to be installed with a dry stack format with no mortar visible.'
- Section 04 40 00** Line 29 & 30, Page 04 40 00-1. Revise to 'Cut stone shall be "Sienna" in the Stack Ledge finish, with Quality water table sill measuring 23-1/2"x3"x2.'
- Section 07 13 00** Omit this section
- Section 08 11 13** Line 23, page 08 11 13-3. Add "**Windows** - Glazing to be installed in accordance to manufacturers specifications and under Section 08 80 00
- Section 08 51 13** Omit this section

**DRAWINGS**

- Sheet A3.2 Detail 1/A3.2 Door and Frame Elevations** revise as follows:
- Change door type E to Aluminum Insulated
  - Change frame type 1 to be 1A
  - Add frame type 1B to be Aluminum insulated with same dimensions shown for frame 1A
  - Change frame type 2 to be Insulated Aluminum
  - Change frame type 3 to be Insulated Aluminum
- Door & Window Schedule:**
- Revise frame for doors: 100-1, 101-1, 102-1, 103-1, 105-1, 106-1 to be 1A
  - Revise frame for door 108-1 to be 1B
- Detail 2/A3.2 Wall Type.** Revise Wall type 6 to include 1/2" Thermax between framing and 6 mil vapor barrier.

END OF ADDENDUM